

# Boat Lashing Process

Curio Pack Sdn Bhd  
Penang Office

A stylized silhouette of a mountain range in shades of teal, located at the bottom right of the slide.

# 40' Flat Rack Container on Trailer



# View From Side



Lashing Points

# Lifting the Boat via Forklift



Note that the forks are positioned at the centre of gravity of the boat. It is also raised by 2 timber blocks to support the boat's trailer. If the boat is without trailer, a cradle has to be made to support the boat and a crane with sling and spreader bar to do the lifting.

# Positioning Is Important



# Timber Bracing

Triangle stoppers for horizontal and side movements



# More Pictures Of Bracings



# Belt Lashings Front and Back

Belt lashings  
boat to trailer

Belt lashings  
boat to  
container





# Wire Rope and Turnbuckle Lashings



Wire rope lashing trailer to container



# More Wire Rope Lashings



# Loading Back to Trailer



# The End

With proper planning, this job only takes 4 hours to complete.

A presentation by Curio Pack Sdn Bhd